


## "Flout" Siphons




### Tanks with 15" draw Siphons



Discharge rate = 72 gpm





#### Notes:

- 1. These chambers are not stock; please allow two weeks notice for delivery.
- 2. Other dose volumes available on a special order basis.
- 3. Volume can be reduced with solid blocks on the inlet end.

#### **SPECIFICATIONS**

Concrete Min. Strength: 4,000 psi at 28 days Reinforcement: #3 Rebar, 10ga. Wire Mesh

Air Entrainment: 6%

Construction Joint: Butyl Rubber Sealant

Pipe Connection: Polylok Seal / SDR 35 Coupler

Weight varies

Load Rating: 300 psf

# PRECAST SIPHON CHAMBER DUAL ALTERNATING DESIGN

#### Woodard's Concrete Products, Inc.

629 Lybolt Road, Bullville, NY 10915 (845) 361-3471 / Fax 361-1050

Page 3C 5/18/12